Summary of Component 2-2

Bridge between Engineering and Construction Works

Thematic International Workshop 2007 on Feasible and Affordable Seismic Constructions
July 18, 2007
World Bank Tokyo Development Learning Center, Tokyo, Japan

Tatsuo Narafu

General Coordinator of R&D Project
Senior Coordinator for International Cooperation,
Building Research Institute Japan (BRI)

Background of R&D

 Earthquakes cause serious damages to human societies





Serious Damages to houses


- Developing countries are more vulnerable because they can not afford to be prepared
- Conventional housing should be focused because it is the main cause of human losses and needs more to be done to be safer





Huge Gap between Engineering and Construction Works

- Survey in Banda Aceh
- Construction works does not meet the requirement of drawings and specifications





Problems

Improper Mixture of Concrete

- Improper mixture ratio/too little cement
- Too much water
- Inadequate placing/No compacting








Problems

Improper Bending Works of Rebar

- No anchorage of walls to columns
- Inadequate placing of hoops








Problems

Improper Bending Works of Rebar

- Inadequate connection
- Feasible detailing is necessary





Proposal of Research and Development Bridge between Engineering and Construction Works

- Purpose
 to introduce engineering approach into non engineered constructions
 to propose recommendations on construction
 works and structural designs
 to propose a simple method to estimate seismic
 strength
- Targeted structure types
 - Confined masonry with brick walls
 - Adobe houses for reference

R&D activities


- Monitoring of construction works in actual construction sites
- Series of experiments on materials and components
- Elaboration of proposals for improvement of construction works with available materials, tools and construction skills
- Elaboration of proposals on structure designs which are feasible and acceptable for construction workers
- Elaboration of proposals on simple and easy method to estimate seismic strength by simple and low cost experiments

Activities in 2006

Monitoring of construction works of Adobe housed of JICA Pilot Project in Peru

Adobe housed of JICA Pilot Project


- Highly engineered adobe houses
- Very precise construction works
- Complicated procedures
- Simplification/rationalization is recommendable





Activities in 2007

- Monitoring activities by Japanese engineers on confined masonry in Indonesia and Peru
- Series of experiments of materials and components
- Proposal of simple method for estimation of seismic strength
- Discussion and elaboration of recommendations



BRI and our partners expect

active participation and contribution

Such as

*offering experience and expertise

*proposing collaborative works

such as monitoring activities and experiments

Thank you